

# CONTENTS

DISCLAIMER	i
FOREWORD	ii

## **1 Roles and responsibilities** **1**

1.1	Introduction	1
1.2	Types of stakeholders and their roles in the construction process	2
1.2.1	Airport operators	2
1.2.2	Third-party consultants and contractors	3
1.2.3	Aircraft operators	3
1.2.4	Air navigation service providers	3
1.2.5	Civil aviation authorities	4
1.2.6	Other tenants and service providers	4
1.2.7	Communities in the airport vicinity	4

## **2 Regulatory framework** **5**

2.1	Introduction	5
2.2	ICAO	5
2.3	Airport services manual part 9, doc 9137	6
2.4	Aerodrome manual	6
2.5	PANS—aerodromes, doc 9981	6
2.6	Airport operators	6
2.7	Local government approvals	6
2.8	Other references	7

## **3 Types of work** **8**

3.1	Construction locations	8
3.1.1	Landside works	8
3.1.2	Airside works	9
3.2	Construction objects	9
3.2.1	Civil works	9
3.2.2	Building works	10
3.3	Construction attributes	10
3.3.1	New construction	10
3.3.2	Repair or improvement	10
3.4	Construction periods	11
3.4.1	Short term	11
3.4.2	Long term	11

## **4** Pre-construction **12**

4.1	Introduction	12
4.2	Application phase	13
4.3	Planning phase	14
4.3.1	Identify the area affected by the construction and supplemental activities	14
4.3.2	Define the activities	15
4.3.3	Sequence the activities	15
4.3.4	Estimate activity resources	15
4.3.5	Estimate activity duration	15
4.3.6	Define the stakeholders and services affected	16
4.3.7	Define the type of conduct of activities	16
4.3.8	Plan the schedule	17
4.3.9	Perform risk assessment	18
4.3.10	Perform operational impact assessment	20
4.3.11	Develop a project management plan	21
4.4	Communication phase	27
4.5	Approval phase	28
4.6	Notification phase	29
4.6.1	NOTAMs	29
4.6.2	AIP amendments	29
4.6.3	Airport operation notices	29
4.6.4	Work instruction to ATC	29
4.6.5	Work instructions to operational and safety staff	30
4.7	Implementation phase	30
4.7.1	Managing the contractors	30
4.7.2	Facilitation for the contractors	31

## **5** During construction **33**

5.1	Physical control	33
5.1.1	Closure areas	33
5.1.2	Movement of vehicles and equipment	35
5.1.3	FOD control	36
5.2	Aircraft movement area closure planning and arrangement	37
5.2.1	Closure planning	37
5.2.2	Closure arrangement	39
5.3	Daily pre-works meeting	40
5.4	Technology application for works activities management	40
5.4.1	Pre-works planning	40
5.4.2	Commencing works	41
5.5	The effectiveness of safety audits/inspections	41
5.5.1	Scheduled safety audits	41
5.5.2	Site Safety Inspections (SSIs)	41
5.6	Continuous improvements and application of the risk register	42

## **6** Handover and commissioning **44**

6.1	Inspection and approval	44
6.1.1	Appointment of inspector	45
6.1.2	Roles of inspector	45
6.1.3	Types of inspection	45
6.1.4	Contents of inspection	45
6.1.5	Inspection by CAA or local government	46
6.2	Handover	46
6.3	Dissemination of information	47
6.3.1	Notification of commissioning	47
6.3.2	Notification of “out of service”	47
6.4	Preparations	47
6.4.1	Setting up operational plans	47
6.4.2	Trial operations	48
6.5	Commissioning	48

## **7** Construction area safety measures **49**

7.1	Construction area prohibitions	49
7.1.1	Smoking	49
7.1.2	Food and/or beverage	49
7.1.3	Personal electronic device usage	49
7.1.4	Operation of metal tracked vehicle/equipment	49
7.2	Construction safety requirements	50
7.2.1	Personal protective equipment	50
7.2.2	Safety cones	51
7.2.3	Caution tapes	51
7.2.4	High-density drums	52
7.2.5	Low-profile barriers	52
7.2.6	Water barricades	53
7.2.7	Fences	53
7.2.8	Safety mesh	54
7.2.9	Mobile safety barriers	54
7.2.10	Railing barriers	55
7.2.11	Scaffolds	55
7.2.12	Signs	56
7.2.13	Obstruction flags	58
7.2.14	Lighting	58

## **8** Lessons learned **59**

8.1	Introduction	59
8.2	Pre-construction phase	59
8.3	During construction phase	62
8.4	Commissioning and post-construction handover	64

## **9 Case studies 68**

9.1	Runway rehabilitation at Dubai International Airport	68
9.1.1	Roles and responsibilities	68
9.1.2	Regulatory framework	69
9.1.3	Types of work	69
9.1.4	Pre-construction	70
9.1.5	During construction	71
9.1.6	Operational readiness and transfer	74
9.1.7	Post implementation review (lessons learned)	74
9.2	Terminal facility improvement for A380 operations at Incheon Airport	75
9.2.1	Construction overview	75
9.2.2	Actions in pre-construction	75
9.2.3	Actions during construction	78
9.2.4	Return to operation	79
9.3	Apron excavation for access railroad for Incheon Airport	79
9.3.1	Construction overview	80
9.3.2	Actions in pre-construction	80
9.3.3	Actions during construction	82
9.3.4	Return to operation	83
9.4	Temporary markings and signage at paris-charles de gaulle	83
9.4.1	Paris-CDG and airfield safety during construction	83
9.4.2	Taxiway closure	84
9.4.3	Taxilane with a dead end	85
9.4.4	Closure of runway entrance/exit taxiways	86
9.4.5	Runway closure	87
9.4.6	Shortened runway	89
9.4.7	Temporary information signage	91
9.4.8	Non-aviation signage	95

## **10 Annexes 98**

Annex 1	Examples of accidents and incidents related to construction	98
Annex 2	Example of an airside work permit flow	99
Annex 3	Example of an airfield works permit form	100
Annex 4	Abbreviations	101